

AIR SPRING ASSEMBLY

Two stations with manual feeding (air spring and damper), connected with automatic processes. Final test station with seading check.

■ REQUIREMENTS

- Poke-Yoke of mounting parts
- leakage test

■ PROCESS

- Loading air spring and damper
- Insert the damper into air spring
- Assembly by screwing
- Filling air and helium

■ MACHINE DATA

Place of manufacture: China

Industry: Automotive

Operating location: China

Year of construction: 2022

